BRUHATH BANGALORE MAHANAGARA PALIKE

Rajarajeshwari Nagara Division

SCHEDULE-B

Name of Work :Construction of RCC Drain at 11th Cross of Muthyala nagara in ward no 17

Agency			Sri G VASU		
Sl No.	Qty	Item Description	Unit	Rate	
				In Figures	In Words
1	2	3	4	5	6
1	297.00	Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	cum	239.00	Rupees Two Hundred Thirty Nine Only
2	297.00	Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	114.00	Rupees One Hundred Fourteen Only
3	49.50	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregate @0.85 cum and fine aggregate @0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4501.00	Rupees Four Thousand Five Hundred One Only
4	94.50	Providing andlaying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed -2008, machine mixed, concrete laid in layres not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls, walls (any thickness) includng attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5916.00	Rupees Five Thousand Nine Hundred Sixteen Only
5	61.43	Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wasstge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	qtl	7742.00	Rupees Seven Thousand Seven Hundred Forty Two Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

	Qty	Item Description	Unit	Rate	
				In Figures	In Words
	2	3	4	5	6
6	720.00	Providing and removing centering, shuttering, strutting proppoing etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters butresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm	285.00	Rupees Two Hundred Eighty Five Only
7	270.00	Providing 10 cm thick granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.	sqm	608.00	Rupees Six Hundred Eight Only
8	270.00	Providing one line dressing to granite stone slabs / granitestone masonary as per specifications	sqm	460.00	Rupees Four Hundred Sixty Only
9	1428.00	Providing chamfering edges to stone slabs 2.5 cms, wide as per specifications (only chamfered length shall be recorded)	rmt	30.00	Rupees Thirty Only
10	667.00	Providing and fixing Pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with toop and bottom wideth 114 and 165 mm respectively 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, includng form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unoading lead and lift transportatin etc, complete.	nos	280.00	Rupees Two Hundred Eighty Only
11	135.00	Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications	sqm	25.00	Rupees Twenty Five Only
12	135.00	Providing and applying floor painting with ready mix paint in two coats (excluding primer coat) on new concrete/asbestos cement sheet/plastered surfaces brushing to give an even shade after preparing the surface after througly cleaning oil dirt, dust other foreign matter and sand papering including cost of all materials, labour complete as per specifications.	sqm	47.00	Rupees Forty Seven Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP